BRUHATH BANGALORE MAHANAGARA PALIKE,
Office of the Executive Engineer Dasarahalli Division,
Schedule-B

NAME OF WORK: Community Property maintenance (including parks) at ward no 15 in Dasarahalli

Sl. No	Description of work	Unit	Qty	Rate quoted by the ContractorJ Naveen (N J INFRASTRUCTURES PROP J NAVEEN)	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	Cum	47.84	500.0	23920
2	Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density)	Cum	53.82	400.0	21528
3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	25.4	5900.0	149860

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner

4	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	Sqm	115	1400.0	161000
5	Providing and fixing Pre Cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400 mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including form work, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete.	Nos	142	500.0	71000
6	Supply & fixing of Bicycle : All products must tested and certified to meet EN 16630 safety standards with GS test mark. TheEN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGSonly. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN 16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN 16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to	Each	1	160000.0	160000

Signature of the Contractor

Executive Engine
Dasarahalli Divisi

EXECUTIVE ENGINEE
Bruhat Bengaluru Mahanagara Pali
Dasarahalli Division, Bengaluru-73

Scanned by CamScanner

7	Supply & fixing of Pull Down Challenger : All products must tested and ertified to meet EN 16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 ertificates must be on the name of a supplier who has carried out a minimum of loo public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These N16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification s mandatory during technical bid. All products must clearly display the 65 mark as has been issued in the EN 16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are	Each	1	299000.0	299000
8	Supplying & fixing of Big Shoulder Wheel : All products must tested and certified to meet EN16630 safety standards with GS test mark The EN16630 certificates must be issued by a reputed notified international Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & 65 Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN 16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are	Each	1	160000.0	160000

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-57

Scanned by CamScanner

9	Supplying & Fixing of Seated Chest Press : All products must tested and certfied to meet EN 16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. Alt products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are	Each	1	295000.0	295000
10	Supplying & fixing of Self Weighted Rower: All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified international Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certIficates must be in the name of a supplier who has carried out a minimum of 100 public park poject in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN 16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issu cd in the EN 16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are	Each	1	230000.0	230000

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engine
Dasarahalli Divisi
BBM

Scanned by CamScanner

13	Supply & fixing of HD Waist Twister All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must he issued by a reputed notified International Certifying Body such is IP EMA, TUV, CPSC, or SGS only. The GS mark-EN16630 certifiates must bu in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN 16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved	Each	1	188000.0	188000
14	Supply & fxing of Double Ski Walker : All products must tested and certified to meet EN 16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in india with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & 65 Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are	Each	1	299000.0	299000

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner